

SCAN HERE



PR-2023-0606-121904

OP 6/8/23

TO PPD



Republic of the Philippines  
**VISAYAS STATE UNIVERSITY**  
 Visca, Baybay City, Leyte

## PURCHASE REQUEST

PPMP No. : 176-2-1557-2023-4-0-3

PR No.: GF-2023-06-00951

Date: 06-06-2023

Dept./Office: **ODPP**

Category: **Construction  
and Electrical Supplies**

Section/End-User: **Rafael Rosario A. Juntilla**Project Title/Code: **Genomics Laboratory/2023**Funding Source: **General Fund - CO**

Item #	Item Description	Unit	Qty	Unit Cost	PAR/ICS	Total Cost
1	1 Unit 25KVA Diesel Genset with Manual Transfer Switch, 150 amp	unit	1	450,000.00		450,000.00

### Specification:

1 Unit 25KVA Diesel GenSet with Manual Transfer Switch, 150 amp

Standby Rating: 25KVA/25Kw

Voltage Output: 220Vac

Ampere Rating (Full Load): 113.0 amp

Phase/Frequency/Speed: Single Phase/^0 Hz/1800 rpm

DIESEL ENGINE, In-line, 4 stroke cycle, electronic actuated governor, water radiator cooling system, electric starting. Close coupled to a?C-brushless Alternator, self-exciting, self-regulating, insulation class H, single bearing and with built in automatic Voltage Regulator.

DIGITAL CONTROL PANEL with display of all parameters; Equipped with Automatic Shut-Off sensors for engine low-oil pressure, high coolant temperature, over-crank, over/under speed and over/under frequency. Also equipped with EMERGENCY Push Button Shut-Off Switch.

SOUND PROOF WEATHER PROTECTIVE CANOPY- mounted on a heavy-duty steel frame with vibration isolators, base fitted fuel tank with capacity capable for eight (8) hours continuous operations at full load.

<b>TOTAL</b>						<b>450,000.00</b>
--------------	--	--	--	--	--	-------------------

Purpose: For Genomics Laboratory

Checked by:	Funds Available:		
<b>PHILOEM D. GALUPO</b>	<b>ALICIA M. FLORES</b>		
TWG - Construction and Electrical Supplies	HEAD, BUDGET OFFICE		
Signature:	Requested by:	Noted by:	Approved by:
Printed Name: <b>RAFAEL ROSARIO A. JUNTILLA</b>	<b>MARLON G. BURLAS</b>	<b>EDGARDO E. TULIN</b>	<b>EDGARDO E. TULIN</b>
Designation: <b>END USER</b>	<b>UNIT HEAD, PROJECT LEADER</b>	<b>PRESIDENT, VSU</b>	<b>6/8/23</b>