

# Republic of the Philippines VISAYAS STATE UNIVERSITY

Visca, Baybay City, Leyte

### **PURCHASE REQUEST**

PPMP No.: PPMP-2024-062124-0202

PR No.: STF-2024-09-01649

Date: 09-05-2024

Dept./Office: CVM

Section/End-User: Joel M. Israel

Category: Construction and Electrical Supplies

Funding Source: Special Trust Fund

Project Title/Code: CVM Laboratory Share 1

Item #	Item Description	Unit	Qty	Unit Cost	PAR/ICS	Total Cost
1	Electrical Panel board, (Three Phase), Surface mounted, bolt-on type	piece	1	80,000.00		80,000.00

#### Specification:

• Type: Electrical Panel Board

• Phase: Three Phase

Mounting: Surface MountedConstruction: Bolt-On Type

Holes: 20Components:

O Center Main:

■ 1 pc.: 150 AT/150 AF, 3P, 18 KAIC, @ 240V MCCB

Branches:

14 pcs.: 20 AT, 2P, 8 KAIC, @ 240V MCCB
 4 pcs.: 30 AT, 3P, 8 KAIC, @ 240V MCCB

2	Electrical Tape (Rubber)	pcs	2	180.00	360.00	
	0 15 11			100.00	360.00	

#### Specification:

• Type: Rubber


Dimensions: 0.8 x 19mm x 8m

· Color: Any color

3	Electrical Wire, THHN/THWN AWG 2/0(60 mm²), Stranded wire		300	560.00	168,000.00
4	Electrical Wire, THHN/THWN, AWG 6 (14 mm2), Stranded Wire 600 volts, 150 meters per roll	rolls	1	18,000.00	18,000.00
5	Electrical, Ground rod with clamp, 5/8" diameter x 4'	рс	1	550.00	550.00
6	Electrical, Junction Box (Octagonal) with cover, PVC	pcs	2	50.00	100.00
7	Safety Breaker 60ATF, 2P, 12KAIC,240V MCB	set	1	700.00	700.00

TOTAL 267,710.00 Purpose: VTH Power Supply Installation (Converting Single Phase to Three Phase Power Supply Checked by: Funds Available: 1011/6 CLINT C. SARVIDA ALICIA W. FLORES LUNIFAST TWG - Construction and Electrical Supplies HEAD, BUDGET OFFICE Prepared by: Noted by: Approved by: Signature: JOEL M. ISRAEL Printed Name: HARVIE P. PORTUGALIZA PROSE IVY G. YEPES Designation: UNIT HEAD, PROJECT LEADER PRESIDENT, VSU

☑ Original PPMP
Revised (Changed items, same budget)
☐ Supplemental





## PROJECT PROCUREMENT MANAGEMENT PLAN (PPMP)

CY 2024

Unit/Office/Dept/Div:

College of Veterinary Medicine

Project Code:

CVM Laboratory Share 1

Three Phase Power Supply

Purpose:

VetMed Hospital Building Service Wire and X-Ray Equipment Power Supply Installation (Converting Single Phase to

Funding: PPMP #:

Total Budget

: 350,000.00

STF

PPMP-2024-

062124-0202

				Estimated	Schedule/Milestone of Activities (in quantities)											
General Description		Unit	Unit Cost	Budget	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Construction and Electrical Supplies				700.00												1
Safety Breaker 60ATF, 2P, 12KAIC,240V MCB	1	set	700.00	700.00			-	-								1
Electrical, Ground rod with clamp, 5/8" diameter x 4'	1	рс	550.00	550.00			-				-					2
Electrical Tape (Rubber)	2	pcs	180.00	360.00											_	2
Electrical Tape (Rubber)  Electrical, Junction Box (Octagonal) with cover, PVC	2	pcs	50.00	100.00							<del>                                     </del>			-		-
Electrical Panel board, (Three Phase), Surface mounted, bolt-on type	1	piece	80,000.00	80,000.00								_				300
Electrical Wire, THHN/THWN AWG 2/0(60 mm²), Stranded wire	300	meters	560.00	168,000.00												300
Electrical Wire, THHN/THWN, AWG 6 (14 mm2), Stranded Wire 600 volts, 150 meters per roll	1	rolls	18,000.00	18,000.00			·				-			-	-	+-
Sub-Total				267,710.00		-	+	+	-	+	+		+		<b>†</b>	
Grand Total	-			267,710.00									_			

Prepared by:

JOEL M. ISRAEL

Submitted by:

HARVIE P. PORTUGALIZA

Unit Head/Project Leader

Date: 08/27/2024

\*Funding Sources: General Fund(GF), Trust Fund(TF, Special Trust Fund(STF), IGP, Supplemental or Augmentation

Note: Please make a separate PPMP for each funding source.

Categorize the entries such as Office Supplies, Office Appliance & Equipment, Office Furniture, Laboratory Supplies, IT Equipment, Construction & Electrical Supplies, Farm & Agricultural Supplies, Feeds & Feed Ingredients, Medical & Dental Supplies, Auto Supplies