

10: FVM

SCAN HERE



PR-2025-0718-285946

OP 7/23



Republic of the Philippines
VISAYAS STATE UNIVERSITY
 Visca, Baybay City, Leyte

PURCHASE REQUEST

PPMP No. : **PPMP-2025-070325-1281**PR No.: **TF-2025-07-00864**Date: **07-18-2025**Dept./Office: **FVM**Category: **Construction
and Electrical Supplies**Duration: **2024-12-01
to**Section/End-User: **Heherson A. Luza**Project Title/Code: **20201050 -
10.6.33 - B****2026-11-30**Funding Source: **Trust Fund**

Item #	Item Description	Unit	Qty	Unit Cost	PAR/ICS	Total Cost
1	Labor and Materials for the FVM-Central Laboratory Room Refurbishment/Improvement	lot	1	350,000.00	HARVIE P. PORTUGALIZA	350,000.00

Specification:

A. Biosafety Laboratory:

I. Glass Partition and Door

Specs:

- Fixed Glass Partition Wall (5.50 M x 2.20 M), 6mm thk Glass;
- Aluminum Frame (50 mm x 75 mm), Grey Powder Coated Finish
- Sliding Glass Door (Single Panel) (1.00 M x 2.10 M), 6mm thk Glass;
- Aluminum Frame (50 mm x 50 mm), Grey Powder Coated Finish

Quantity: 1

Unit: Lot

B. Island Working Table:

Specs:

Carpentry:

- Marine Plywood, 3/4"
 - Qty: 5 sheets
- Assorted Common Wire Nails (1", 1 1/2")
 - Qty: 2 kg
- Wood Glue
 - Qty: 0.5 kg

Painting:

- Wood Putty/Cast
 - Qty: 1 kg

- Wood Primer, Flat Finish
 - Qty: 1 gallon
- Enamel Paint, Gloss Finish
 - Qty: 2 gallons
- Paint Thinner
 - Qty: 2 gallons
- Assorted Sanding Pad (#120, #220)
 - Qty: 20 sheets
- Paint Brush 2"
 - Qty: 5 pcs
- Paint Brush 4"
 - Qty: 5 pcs

Hardware:

- Cabinet Handle – Stainless Steel 3"
 - Qty: 4 sets
- Concealed Cabinet Hinges, Full Overlay, Soft Closing
 - Qty: 4 sets
- Drawer Slide – Bearing Type 22", Soft Closing
 - Qty: 10 sets
- Drawer Pull/Handle
 - Qty: 10 sets
- Stainless Tube - 1" Diameter, 2.0 M Length
 - Qty: 2 Lengths

Electrical Works:

- Convenience Outlet, 2 Gang, 3-Pin Universal
 - Qty: 1 set
- Threaded Wire Conductor, 5.0 mm2 THHN
 - Qty: 1 box
- Electrical Utility Box, 2" x 4"
 - Qty: 22 pcs
- Rigid Plastic Conduit, ¾" Diameter
 - Qty: 10 L
- Tubular Light, T5 LED, 8W – Cool White
 - Qty: 6 pcs
- Single Gang Switch
 - Qty: 1 set

C. Side Counter and Shelves:

Specs:

Counter:

- Portland Cement, Type I
 - Qty: 4 pcs

- Fine Sand
 - Qty: 1 cu.m.
- Crushed Gravel, ¾"
- Qty: 1 cu.m.
- Hollow Block, 4" Thk
 - Qty: 8 pcs
- Deformed Reinforcing Bars, 10 mm Diameter, 6M Length, Grade 33
 - Qty: 4 pcs
- Hacksaw Blade
 - Qty: 2 pcs
- Concrete Sealer
 - Qty: 1 gallon

Shelves:

- Marine Plywood, ¾"
- Qty: 7 sheets
- Assorted Common Wire Nails (1", 1 ½")
 - Qty: 5 kgs
- Wood Glue
 - Qty: 0.5 kg
- Wood Putty/Cast
 - Qty: 1 kg
- Wood Primer, Flat Finish
 - Qty: 1 gallon
- Enamel Paint, Gloss Finish
 - Qty: 1 gallon
- Paint Thinner
 - Qty: 1 gallon
- Assorted Sanding Pad (#120, #220)
 - Qty: 20 sheets
- Paint Brush, 2"
 - Qty: 5 pcs
- Paint Brush, 4"
 - Qty: 5 pcs

Hardwares:

- Stainless Tube, 1" Diameter, 2.5 M Length
 - Qty: 2.0 Lengths
- Concealed Hinges, Full Overlay
 - Qty: 16 pcs
- Concealed Hinges, Half Overlay
 - Qty: 8 pcs
- Cabinet Handle - Stainless Steel 3"
 - Qty: 22 pcs
- Drawer Guide, Heavy Duty, Ball Bearing, Full Extension 18"
 - Qty: 10 sets

D. Safety Shower Assembly

Specs:

Plumbing Works:

- Safety Shower with Eye Wash
 - Qty: 1 set
- Water Pipe - 1" PPR, PN10
 - Qty: 4 Lengths
- Coupling - 1" PPR, PN10
 - Qty: 5 pcs
- 90 Elbow - 1" PPR, PN10
 - Qty: 3 pcs
- Male Adaptor - 1" PPR, PN10
 - Qty: 1 pc
- Floor Drain 4"
 - Qty: 1 pc
- PVC P-Trap – 2" Diameter, S1000
 - Qty: 1 pc
- PVC Pipe - 2" Diameter, S1000
 - Qty: 3 Lengths

Painting Works:

- Latex Paint, Green, Semi-Gloss
 - Qty: 10 Gallons
- Assorted Sanding Pad (#120, #220)
 - Qty: 50 sheets
- Paint Roller 12"
 - Qty: 10 pcs
- Paint Roller Tray (W – 280mm x H – 360mm x D - 75mm)
 - Qty: 5 pcs

Other requirements:

- Labor for refurbishment/ improvement included.
- Labor for electrical and water installation included.

Floor plan:



