

10, PPO

SCAN HERE



PR-2025-0709-284208

OP 7/24



Republic of the Philippines
VISAYAS STATE UNIVERSITY
Visca, Baybay City, Leyte

PURCHASE REQUEST

PPMP No. : **PPMP-2025-070325-1277**

PR No.: **STF-2025-07-00820**

Date: **07-10-2025**

Dept./Office: **PPO**

Category: **Construction
and Electrical Supplies**

Section/End-User: **Alfe Mae Ann E. Marinay**

Funding Source: **Special Trust Fund - MOOE**

Project Title/Code: **Housing Re-wiring**

Item #	Item Description	Unit	Qty	Unit Cost	PAR/ICS	Total Cost
1	Electrical Wire, THHN/THWN, AWG 8 (8mm²), Stranded, 150 meters/box	boxes	7	9,750.00		68,250.00

Specification:

- **Type:** THHN/THWN, Building Wire
- **Gauge:** AWG 8 (8mm²)
- **Stranding:** Stranded with Nylon Insulation
- **Length:** 150 meters/box
- **Certification:** UL listed

2	Machine bolt, 5/8" x 10" with locknut & washer	pcs	60	150.00		9,000.00
3	Electrical Entrance Cap, 3/4"	set	50	100.00		5,000.00
4	Electrical Conduit, (PVC) 25mm diameter	pcs	200	140.00		28,000.00
5	Electrical, PVC long sweep elbow, 3/4" x 90deg	pcs	200	30.00		6,000.00
6	Spool Insulator Porcelain type	pcs	100	80.00		8,000.00
7	Machine Bolt 5/8 x 12" with Lock nut & washer	set	60	200.00		12,000.00
8	PVC Clip 3/4 heavy duty	pcs	800	12.00		9,600.00
9	Black screw #1 pointed	pcs	500	2.00		1,000.00
10	Electrical Stranded Wire, THHN/THWN-2 Wire, AWG #6 (14 mm²)	box	7	20,000.00		140,000.00

Specification:

- 600 V/90 Degrees Celsius
- Moisture and Heat Resistant, Flame-Retardant, for dry and wet applications
- PVC-Insulated and Nylon-Jacketed
- Lead-Free
- ROHS-2 Compliant
- 150 meters/coil
- 99.9% Pure Copper


• Green						
11	Electrical tape super adhesive	roll	100	85.00		8,500.00
12	#14 AWG/2.0mmsq THHN stranded copper wire fire retardant	boxes	18	3,800.00		68,400.00
13	#12 AWG/3.5mmsq THHN stranded copper wire fire retardant	boxes	18	4,800.00		86,400.00
14	Secondary Rack single phase w/ insulator	pc	150	280.00		42,000.00
15	#8AWG / 8mm2 Service Entrance Conductor ACSR stranded 2C twisted	meters	600	30.00		18,000.00
16	#4AWG / 22mm2 Aluminum Insulated Wire 600V ACSR single core	meters	1500	145.00		217,500.00
17	Screw insulator for #4AWG service drop wire	pcs	150	100.00		15,000.00
18	PVC Orange Male Adapter with Lock Nut 3/4"	set	200	10.00		2,000.00
19	Hexagonal Steel Pole 20 feet	length	30	35,000.00		1,050,000.00
20	#6AWG / 14mm2 service entrance conductor ACSR stranded 2C twisted	meters	800	40.00		32,000.00
21	Secondary Rack (2 spool) with insulator	pcs	150	300.00		45,000.00

Specification:

- With Insulator, Heavy Duty

22	Electrical Circuit Breaker, 30 amp (Plug-in) 2Poles	pcs	30	500.00		15,000.00
23	Electrical Circuit Breaker, 20 amp (Plug-in) 2Poles	pcs	30	450.00		13,500.00
24	Electrical Circuit Breaker, 15 amp (Plug-in) 2Poles	pcs	30	450.00		13,500.00
TOTAL						1,913,650.00

Purpose: Housing Rewiring

Checked by:  CLINT C. SARVIDA		Funds Available:  ALICIA M. FLORES	
TWG - Construction and Electrical Supplies		HEAD, BUDGET OFFICE	
Signature:	Prepared by:  ALFE MAE ANN E. MARINAY	Noted by:  MARLON G. BURLAS	Approved by:  PROSE IVY G. YEPES
Printed Name:			
Designation:		UNIT HEAD, PROJECT LEADER	PRESIDENT, VSU